Abstract estimate for constructing Type Design Colony houses in the Irwin Canal Agricultural Colony.

No.	Items of work	Unit	Rate	Quantity for one house	Cost for one house	Cost for 10 houses
1	Earthwork excavation	C.yd.		21		
2	Stone in clay in foundation and basement	C.ft.		725		
3	Burnt brick in clay in superstructure	,,		1,351		
4	Junglewood wrought and put up ..	,,		37		
5	Roofing with 1st class Mangalore tiles on teakwood reepers ..	Sqr.		8·5		
6	Ridge tiles set in mortar ..	R.ft.		84		
7	Teakwood door frame and junglewood shutters with fittings, complete	Sq.ft.		90		
8	Teakwood window frame and teakwood shutter with iron bars, etc., complete	Sq.ft.		54		
9	Trellis work in front with hoop iron and junglewood frame work ..	Sq.ft.		72		
10	Plastering with mortar and whitewashing, 2 coats	Sqr.		7·8		
11	Mud plastering and whitewashing inside	,,		20·3		
12	Flooring with gravel well rammed and cow dung wash	,,		4·3		
13	Burnt stone slabs 4″ thick including fixing	Sq.ft.		122		
14	Painting wood work	L. S.				

T. G. RAMA IYER,
Director of Agriculture.

PRIVATE ADVERTISEMENTS.

GOVERNMENT OF MYSORE, STORES PURCHASE COMMITTEE, BANGALORE.

No. S. P. C. 6151, *dated 3rd September* 1940.

NOTICE.

Enquiry No. 4217.

Sealed tenders will be received by the Secretary, Stores Purchase Committee, for the supply of Special uniform articles required for the Mysore Government Police, Military, and other Departments, during the year 1940-41, upto the 30th of September 1940.

Intending tenderers may, on application to the Secretary, Stores Purchase Committee, obtain the requisite tender forms on which tenders should be submitted. Applications should be accompanied by a cash remittance of Rs. 3 which is the price fixed for a set of forms and which is not refundable.

Cheques and postage stamps will not be accepted towards the cost of forms nor will the forms be sent by V. P. P.

By Order,
MIR SAFDAR HUSSAIN,
Secretary,
Stores Purchase Committee.